

1/17/2017

ADDENDUM NO. 7
TO THE BID DOCUMENTS
(construction plans and bid package)
FOR THE
FRIENDSHIP FOREST WILDLIFE SANCTUARY
PARK RENOVATION PROJECT

Questions Received:

- 1) Please confirm there are only 3 removable bollards and which line item do they go to? There is no line item in schedule of values
- 2) On the existing Granit curb install, can you change the units to LF instead of SY?
- 3) Will we be responsible for any structural engineering or permitting for the parking lot wall?
- 4) Will the city be providing the stone for the walls?
- 5) In your "Wood Railing" line item, please specify where this goes. Is the steel pickets on the platforms to be included in this?

Response to Questions:

1. Yes, there are only 3 removable bollards for this project. As noted on our schedule of values; "Contractor is responsible for submitting pricing for all items shown within the contract documents, regardless of what is listed within the schedule of values." You may include the cost for these items in any pay item as you deem appropriate.
2. The granite curb installation consists of laying pieces of leftover granite curb flat on the ground in several areas (at the direction of the city's project engineer). This is not a linear application, but areas of installation, so SY is appropriate.
3. Project plans were approved through an internal review and permitting. No additional permitting or structural engineering will be required by the city.
4. The granite for the walls is to be purchased by the Contractor (Note for granite quarry is located on C-24, at bottom of "Parking Lot Site Wall Detail".)
5. The wood railing is the alternate to the base bid cor-ten guardrail (refer to the Schedule of Bid Items – Bid Alternate #2; page 20). The wood railing is on both sides of the boardwalk(s) and along ramp/platforms. The steel posts are part of the base bid.